



AS-BUILT SUBMITTAL REQUIREMENTS

The As Built submittal **shall** contain the following information:

- A. CSV files with Grid Coordinate Data to a tenth of a foot in NAD83 coordinated system, generated by a registered surveyor that contain, at a minimum, the point number, northing, easting, elevation, description/point name, feature type, feature material, and feature size. A minimum of two (2) CAP existing ROW property/boundary monuments shall be tied by the Licensee, its agents and/or contractor, and included in the submitted CSV file. CAWCD will provide the location of the closest monuments to the project area upon written request.
- B. Survey points with digital photos must be taken every one hundred (100) feet or any point where there is a change in either the vertical or horizontal alignment. The photos need to be labeled to match the point information and submitted with the survey information.
- C. A complete set of drawings signed, sealed, and dated by a Professional Engineer or Land Surveyor registered in the State of Arizona that include the precise location and installation specifications of the utility, facility and/or structure by recording any deviation from the original design drawings. The horizontal and vertical datum information must also be included. All drawings must also show the CAP property boundary and License/Easement limits.
- D. Complete sets of As-Built drawings shall be submitted in the quantities and formats stated below:
 - Three sets of half size (11" x 17") hard copies,
 - electronically on a CD-R a PDF set of the drawings, and electronically on a CD-R in CSV format

The As Built submittal should be sent to:

Central Arizona Project
Lands Department
23636 N. 7th Street
Phoenix, AZ 85024

Please direct any questions to the Lands Department by phoning (623) 869-2555 or via email at 2555@cap-az.com.